Hattiesburg Public Safety Complex Hattiesburg, Mississippi

FORM OF PROPOSAL DATE: 01/03/2019 PROPOSAL FROM: Hanco Corporation (List Company Name) TO OWNER: CITY OF HATTIESBURG HATTIESBURG, MISSISSIPPI

PROJECT: HATTIESBURG PUBLIC SAFETY COMPLEX HATTIESBURG, MISSISSIPPI

Ladies & Gentlemen:

Having carefully examined all Contract Documents and addenda for the construction of the project in caption, the undersigned purposes to furnish all labor, materials and services required for the construction in accordance with these documents for the sum as follows:

Twenty Nine Million Nine Hundred Thousand DOLLARS (\$ 29,960,000.00

<u>TIME</u>: The undersigned agrees to complete the work within <u>720</u> calendar days from the date of the Notice to Proceed issued by the Architect. It is also agreed that this proposal/contract price will be valid for the minimum time of <u>60 DAYS</u> from the date of opening.

ALTERNATES: (SEE SECTION 01 35 00)

A. Alternate Number One: <u>This Alternate adds all labor and materials required for the entire scope of work</u> for public parking on south side of Katie Avenue.

forsano Douran; ELGHT HUNDRED ADD \$ 800,000.

B. Alternate Number Two: <u>This Alternate adds all labor and materials required for the Vehicle</u> <u>Maintenance Building Structure and the required pavement.</u>

Two Million Dollans ADD \$ 2,000,000.00

FORM OF PROPOSAL PAGE 1 OF 3

Albert & McCleskey Associates Archited	cts
November 19, 2018	

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

COST BREAKDOWNS: N/A

UNIT PRICES:

1 de 1 d

Unit prices shall apply to authorized changes in the quantities of items included in the scope of work. These unit prices shall remain fixed as stated below for the duration of the project. During this period, the Owner has the option to issue Change Orders to the Contractor for the construction of all items listed below in the quantities desired at the unit prices.

Unit Price Number One:	Add one duplex outlet with wire/conduit along existing circuit = \$	400	/ each.
------------------------	---	-----	---------

BID SECURITY:

Bid Security in the form of <u>Bid Bond</u> is attached i	n the amount of \$ <u>5%</u>	of Bid
ADDENDA:		
Receipt of the following addenda is acknowledged:		
Addendum No: 1 Dated: 12/11/2018	Addendum No: 4	Dated:12/27/2018
Addendum No: 2 Dated: 12/19/2018	Addendum No:	Dated:
Addendum No: 3 Dated: 12/19/2018	Addendum No:	Dated:
GENERAL CONTRACTOR:		
Mississippi Certificate of Responsibility No: 10558-MC		
Resident Contractor: Yes		
Non-Resident Contractor*:N/A		
LIST THE FOLLOWING SUBCONTRACTORS THAT YOU IN	TEND TO USE:	
Roofing Subcontractor (Section 07 52 16):		
N/ANDALS		
Glass/Store/ont/Curtain Wall Subcontractor (Sections		30 00):
MIDSOUTH GLASS COMPANY	1	

FORM OF PROPOSAL PAGE 2 OF 3 EXHIBIT A

Albert & McCleskey Associates Architects November 19, 2018 Hattiesburg Public Safety Complex Hattiesburg, Mississippi

Mechanical/Pl mbing Subcontractor(s) (Divisions 22 / 23): Me Kenzie LORDOR

Electrical Subcontractor (Division 26): .

ACCEPTANCE: I certify that I am authorized to enter into a binding contract, if this Proposal is accepted.

Signature: ____

Typed Name & Title: Chris Hudson - President

Company Name: Hanco Corporation

Address: P.O. Box 17678

City, State, Zip Code: Hattiesburg. MS 39404-7678

Phone, Fax, Email: _____601-583-6500 / 601-583-6503 / chudson@hancocorp.com

DIRECTIONS FOR MAILING:

See INSTRUCTIONS TO BIDDERS [SECTION 00 10 00] for mailing directions.

END OF FORM OF PROPOSAL

FORM OF PROPOSAL PAGE 3 OF 3

▲AIA Document A310[™] – 2010

Bid Bond

CONTRACTOR: (Name, legal status and address) Hanco Corporation P O Box 17678 Hattiesburg, MS 39404 SURETY: (Name, legal status and principal place of business) Liberty Mutual Insurance Company 175 Berkeley Street Boston, MA 02116

OWNER: (Name, legal status and address)

City of Hattiesburg 200 Forrest St. Hattiesburg, MS 39401 This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

BOND AMOUNT: Five Percent (5%) of the Amount Bid-----

PROJECT:

(Name, location or address, and Project number, if any) Hattiesburg Public Safety Complex Hattiesburg, MS

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this

3rd

day of

January , 2019

itness

Hanco Corporation (Contractor as Principal) (Title)

2

Liberty Mutual Insurance Company (Seal) (Surety) (Title Kim Barhum, Attorney-In-Fact **MS Resident Agent**

Certificate No. 8047361

Liberty Mutual Insurance Company

The Ohio Casualty Insurance Company

West American Insurance Company

POWER OF ATTORNEY

KNOWN ALL PERSONS BY THESE PRESENTS: That The Ohio Casualty Insurance Company is a corporation duly organized under the laws of the State of New Hampshire, that Liberty Mutual Insurance Company is a corporation duly organized under the laws of the State of Massachusetts, and West American Insurance Company is a corporation duly organized under the laws of the State of Indiana (herein collectively called the "Companies"), pursuant to and by authority herein set forth, does hereby name, constitute and appoint, David R. Fortenberry; Kim Barhum; Richard Teb Jones; Mary J. Norval

all of the city of <u>Hattiesburg</u>, state of <u>MS</u> each individually if there be more than one named, its true and lawful attorney-in-fact to make, execute, seal, acknowledge and deliver, for and on its behalf as surety and as its act and deed, any and all undertakings, bonds, recognizances and other surety obligations, in pursuance of these presents and shall be as binding upon the Companies as if they have been duly signed by the president and attested by the secretary of the Companies in their own proper persons.

INSU VINC INSU 1912 1991

SS

The Ohio Casualty Insurance Company Liberty Mutual Insurance Company West American Insurance Company

David M. Carey, Assistant Secretary

STATE OF PENNSYLVANIA COUNTY OF MONTGOMERY

interest rate or residual value guarantees.

Not valid for mortgage, note, loan, letter of credit,

rate.

currency

On this <u>28th</u> day of <u>March</u>, <u>2018</u>, before me personally appeared David M. Carey, who acknowledged himself to be the Assistant Secretary of Liberty Mutual Insurance Company, The Ohio Casualty Company, and West American Insurance Company, and that he, as such, being authorized so to do, execute the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

IN WITNESS WHEREOF, I have hereunto subscribed my name and affixed my notarial seal at King of Prussia, Pennsylvania, on the day and year first above written.

PAS RY PU

COMMONWEALTH OF PENNSYLVANIA Notarial Seal Teresa Pastella, Notary Public Upper Merion Twp., Montgomery County My Commission Expires March 28, 2021 Member: Pennsylvania Association of Notaries

linesa Pastella Teresa Pastella, Notary Public

This Power of Attorney is made and executed pursuant to and by authority of the following By-laws and Authorizations of The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company which resolutions are now in full force and effect reading as follows:

ARTICLE IV - OFFICERS - Section 12. Power of Attorney. Any officer or other official of the Corporation authorized for that purpose in writing by the Chairman or the President, and subject to such limitation as the Chairman or the President may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Corporation to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact, subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Corporation by their signature and execution of any such instruments and to attach thereto the seal of the Corporation. When so executed, such instruments shall be as binding as if signed by the President and attested to by the Secretary. Any power or authority granted to any representative or attorney-in-fact under the provisions of this article may be revoked at any time by the Board, the Chairman, the President or by the officer or officers granting such power or authority.

ARTICLE XIII – Execution of Contracts – SECTION 5. Surety Bonds and Undertakings. Any officer of the Company authorized for that purpose in writing by the chairman or the president, and subject to such limitations as the chairman or the president may prescribe, shall appoint such attorneys-in-fact, as may be necessary to act in behalf of the Company to make, execute, seal, acknowledge and deliver as surety any and all undertakings, bonds, recognizances and other surety obligations. Such attorneys-in-fact subject to the limitations set forth in their respective powers of attorney, shall have full power to bind the Company by their signature and execution of any such instruments and to attach thereto the seal of the Company. When so executed such instruments shall be as binding as if signed by the president and attested by the secretary.

Certificate of Designation – The President of the Company, acting pursuant to the Bylaws of the Company, authorizes David M. Carey, Assistant Secretary to appoint such attorneys-infact as may be necessary to act on behalf of the Company to make, execute, seal, acknowledge and deliver as surely any and all undertakings, bonds, recognizances and other surely obligations.

Authorization – By unanimous consent of the Company's Board of Directors, the Company consents that facsimile or mechanically reproduced signature of any assistant secretary of the Company, wherever appearing upon a certified copy of any power of attorney issued by the Company in connection with surety bonds, shall be valid and binding upon the Company with the same force and effect as though manually affixed.

I, Renee C. Llewellyn, the undersigned, Assistant Secretary, The Ohio Casualty Insurance Company, Liberty Mutual Insurance Company, and West American Insurance Company do hereby certify that the original power of attorney of which the foregoing is a full, true and correct copy of the Power of Attorney executed by said Companies, is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 3rd day of January



20 19 By

INDEX OF DRAWINGS

CIVIL SHEET INDEX

C0.1	CIVIL COVER SHEET, SHEET INDEX, VICINITY MAP, LOCATION MAP & UTILITIES LIST
C0.2 C0.3 C0.4 C0.5	GENERAL NOTES GENERAL NOTES CONT'D, CONSTRUCTION PHASES, ABBREVIATION SCHEDULE & SYMBOL LEGENDS EXISTING TOPOGRAPHIC MAP – NORTH BLOCK EXISTING TOPOGRAPHIC MAP – SOUTH BLOCK
C0.6 C0.7 C0.8	DEMOLITION PLAN – NORTH BLOCK DEMOLITION PLAN – NORTH BLOCK DEMOLITION PLAN – SOUTH BLOCK
C1.0 C1.1 C1.2 C1.3 C1.4 C1.5 C1.6 C1.7 C1.8 C1.9 C1.10 C1.11 C1.12 C1.13 C1.14 C1.15 C1.16 C1.17 C1.18 C1.16 C1.17 C1.18 C1.19 C1.20 C1.21 C1.22	MASTER SITE PLAN SITE & UTILITY PLAN – NORTH BLOCK SITE & UTILITY PLAN – NORTH BLOCK SITE & UTILITY PLAN – SOUTH BLOCK SITE & UTILITY PLAN – SOUTH BLOCK SITE PLAN DETAIL – MEMORIAL PARK SITE PLAN DETAILS – INSERTS SITE PLAN DETAILS – INSERTS SITE PLAN DETAILS – INSERTS SITE PLAN DETAILS – INSERTS SITE PLAN DETAILS – INSERTS GENERAL SITE DETAILS – NSERTS GENERAL SITE DETAILS – NARKINGS & RAISED CROSSWALK GENERAL SITE DETAILS – CURB RAMPS GENERAL SITE DETAILS – CURB RAMPS GENERAL SITE DETAILS – STEPS GENERAL SITE DETAILS – COURTYARD PLAN & SECTIONS GENERAL SITE DETAILS – COURTYARD SECTIONS & ELEVATIONS GENERAL SITE DETAILS – COURTYARD SECTIONS & ELEVATIONS GENERAL SITE DETAILS – FENCE & GATE DETAILS GENERAL SITE DETAILS – FENCE & GATE DETAILS GENERAL SITE DETAILS – FENCE & GATE DETAILS GENERAL SITE DETAILS – FENCE & GATE DETAILS SEWER INSTALLATION DETAILS TRACER WIRE DETAILS
C2.0 C2.1	BUILDING A SEWER MAIN – PLAN & PROFILE BUILDING C SEWER MAIN – PLAN & PROFILE
C3.0 C3.1 C3.2 C3.3 C3.4 C3.5 C3.6 C3.7 C3.8 C3.9	MASTER GRADING PLAN GRADING & DRAINAGE PLAN

INDEX TO DRAWINGS PAGE 1 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

- C3.10 DRAINAGE STRUCTURE SCHEDULES
- C3.11 CONCRETE STORMWATER STRUCTURE DETAILS
- C3.12 CONCRETE STORMWATER STRUCTURE DETAILS C3.13 CONCRETE STORMWATER STRUCTURE DETAILS
- C3.14 CONCRETE STORMWATER STRUCTURE DETAILS
- C3.15 HDPE STORMWATER STRUCTURE DETAILS
- C4.0 STORM WATER POLLUTION PREVENTION PLAN PHASE 1
- C4.1 STORM WATER POLLUTION PROVENTION PLAN PHASES 2 & 3
- C4.2 TEMPORARY VEGETATION SCHEDULE
- C4.3 EROSION CONTROL DETAILS
- C4.4 EROSION CONTROL DETAILS
- C4.5 EROSION CONTROL DETAILS

VOLUME ONE – BUILDINGS A & B

- T1.0 TITLE SHEET & INDEX
- T1.1 GENERAL NOTES
- A0.1 ARCHITECTURAL SITE PLAN
- A1.1 CODE REVIEW PLUMBING TOTALS
- A1.2 FIRST FLOOR LIFE SAFETY PLAN
- A1.3 SECOND FLOOR LIFE SAFETY PLAN
- A1.4 THIRD FLOOR LIFE SAFETY PLAN
- A1.5 MECH. PENTHOUSE/ROOF LIFE SAFETY PLAN
- A1.6 PARTITION TYPES
- A2.0a FIRST FLOOR COMPOSITE FLOOR PLAN A2.0b SECOND FLOOR COMPOSITE FLOOR PLAN A2.0c THIRD FLOOR COMPOSITE FLOOR PLAN A2.1a FIRST FLOOR PLAN - PART A DIMENSION PLAN A2.1b FIRST FLOOR PLAN - PART A REFERENCE PLAN A2.2a FIRST FLOOR PLAN - PART B DIMENSION PLAN A2.2b FIRST FLOOR PLAN - PART B REFERENCE PLAN A2.3a SECOND FLOOR PLAN - PART A DIMENSION PLAN A2.3b SECOND FLOOR PLAN - PART A REFERENCE PLAN SECOND FLOOR PLAN - PART B DIMENSION PLAN A2.4a A2.4b SECOND FLOOR PLAN - PART B REFERENCE PLAN A2.5a THIRD FLOOR PLAN - PART A DIMENSION PLAN A2.5b THIRD FLOOR PLAN - PART A REFERENCE PLAN A2.6a THIRD FLOOR PLAN - PART B DIMENSION PLAN A2.6b THIRD FLOOR PLAN - PART B REFERENCE PLAN
- A3.0COMPOSITE ROOF PLANA3.1aROOF PLAN PART AA3.1bROOF PLAN PART BA3.0ROOF PLAN PART B
- A3.2 ROOF PLAN MISC.
- A4.0aFIRST FLOOR RCP COMPOSITEA4.0bSECOND FLOOR RCP COMPOSITE

INDEX TO DRAWINGS PAGE 2 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

A4.0c A4.1a A4.1b A4.1c A4.2a A4.2a A4.2b A4.3a A4.3b A4.4	THIRD FLOOR RCP COMPOSITE FIRST FLOOR RCP - PART A FIRST FLOOR RCP - PART B COURTROOM ENLARGED RCP SECOND FLOOR RCP - PART A SECOND FLOOR RCP - PART B THIRD FLOOR RCP - PART A THIRD FLOOR RCP - PART B PENTHOUSE & ATRIUM RCP
A5.1 A5.2 A5.3 A5.4 A5.5 A5.6	BUILDING ELEVATIONS BUILDING ELEVATIONS BUILDING ELEVATIONS BUILDING ELEVATIONS BUILDING ELEVATIONS BUILDING ELEVATIONS
A6.1 $A6.2$ $A6.3$ $A6.4$ $A6.5$ $A6.6$ $A6.7$ $A6.8$ $A6.9$ $A6.10$ $A6.11$ $A6.12$ $A6.13$ $A6.14$ $A6.15$ $A6.16$ $A6.17$ $A6.18$ $A6.19$ $A6.20$ $A6.21$ $A6.22$ $A6.23$ $A6.24$ $A6.25$ $A6.26$	BUILDING SECTIONS BUILDING SECTIONS & DETAILS WALL SECTIONS & DETAILS MISC. DETAILS LONGITUDINAL SECTION - PART B WALL SECTIONS & DETAILS
A8.1a A8.1b A8.1c A8.2 A8.3 A8.4 A8.5 A8.6 A8.7	DOOR SCHEDULE & DOOR ELEVATIONS DOOR SCHEDULE & FRAME ELEVATIONS DOOR SCHEDULE WINDOW SCHEDULE & ELEVATIONS WINDOW ELEVATIONS WINDOW ELEVATIONS WINDOW ELEVATIONS WINDOW ELEVATIONS

INDEX TO DRAWINGS PAGE 3 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

A9.0a	FINISH SCHEDULE
A9.0b	FINISH SCHEDULE
A9.0c	THRESHOLD DETAILS
A9.0d	FIRST FLOOR FFP COMPOSITE
A9.0e	SECOND FLOOR FFP COMPOSITE
A9.0f	THIRD FLOOR FFP COMPOSITE
A9.1a	FIRST FLOOR FFP PART A
A9.1b	FIRST FLOOR FFP PART B
A9.2a	SECOND FLOOR FFP PART A
A9.2b	SECOND FLOOR FFP PART B
A9.3a	THIRD FLOOR FFP PART A
A9.3b	THIRD FLOOR FFP PART B
A9.4	PENTHOUSE FFP
A10.1 A10.2 A10.3 A10.4 A10.5 A10.6 A10.7 A10.8 A10.9 A10.10 A10.11 A10.12 A10.13 A10.14 A10.15 A10.16 A10.17 A10.18 A10.19 A10.20	INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS MILLWORK DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS MILLWORK DETAILS MILLWORK DETAILS ENLARGED PLAN & DETAILS
A11.1	STAIR A PLANS, SECTIONS, & DETAILS
A11.2	STAIR A SECTIONS, & DETAILS
A11.3	STAIR S SECTIONS, & DETAILS
A11.4	POLICE LOBBY BRIDGE SECTIONS & DETAILS
A11.5	STAIR C PLAN, SECTIONS & DETAILS
A11.6	STAIR B PLANS & GUARDRAIL DATAILS
A11.7	STAIR B SECTIONS & DETAILS
A11.8	ELEVATOR A PLANS & SECTIONS
A11.9	ELEVATOR B PLANS & SECTIONS
A11.10	MISC. STAIRS & RAMPS

VOLUME TWO – BUILDINGS A & B

S0.1	STRUCTURAL NOTES
SO.2	STRUCTURAL NOTES & DRAWING INDEX
S0.3	STRUCTURAL QUALITY ASSURANCE PLAN
S1.1A	FOUNDATION PLAN - PART A

INDEX TO DRAWINGS PAGE 4 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

S1.1B S1.2A S1.3A S1.3B S1.4A S1.5B S2.0 S2.1 S2.2 S2.3 S2.4 S2.5 S2.6 S2.7 S2.8 S3.0 S3.1 S3.2 S3.3 S3.4 S3.5 S3.6 S3.7 S3.8 S3.9 S3.10 S3.11 S3.22 S3.3 S3.10 S3.11 S3.21 S3.13 S3.14 S3.15 S3.16 S3.17 S3.18 S3.19 S3.20 S3.21 S3.22 S4.0 S4.1 S4.2 S4.3 S4.4 S4.5 S4.6	FOUNDATION PLAN - PART B SECOND FLOOR FRAMING PLAN - PART A SECOND FLOOR FRAMING PLAN - PART B THIRD FLOOR FRAMING PLAN - PART A THIRD FLOOR FRAMING PLAN - PART B ROOF FRAMING & LOBBY ATRIUM PLAN - PART A MECH. P.H. FLR. & ROOF FRAMING PLAN - PART B POLICE LOBBY ATRIUM ROOF FRAMING - PART A PENTHOUSE ROOF FRAMING - PART B FOUNDATION SECTIONS & DETAILS FOUNDATION SECTIONS & DETAILS FRAMING SECTIONS & DETAILS FRA
P0.1 P1.1a P1.1b P1.2a	PLUMBING LEGEND AND ABBREVIATIONS FIRST FLOOR PLAN PART A - PLUMBING FIRST FLOOR PLAN PART B - PLUMBING SECOND FLOOR PLAN PART A - PLUMBING INDEX TO DRAWINGS PAGE 5 OF 10

PAGE 5 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

P1.2b	SECOND FLOOR PLAN PART B - PLUMBING
P1.3a	THIRD FLOOR PLAN PART A - PLUMBING
P1.3b	THIRD FLOOR PLAN PART B - PLUMBING
P1.4a	ROOF PLAN PART A - PLUMBING
P1.4b	ROOF PLAN PART B - HVAC
P4.1	PLUMBING RISERS
P5.1	PLUMBING DETAILS
P6.1	PLUMBING SCHEDULES
FP1.1a	FIRST FLOOR PLAN PART B - FIRE PROTECTION
FP1.1b	FIRST FLOOR PLAN PART B - FIRE PROTECTION
FP1.2a	SECOND FLOOR PLAN PART A - FIRE PROTECTION
FP1.2b	SECOND FLOOR PLAN PART B - FIRE PROTECTION
FP1.3a	THIRD FLOOR PLAN PART A - FIRE PROTECTION
FP1.3b	THIRD FLOOR PLAN PART B - FIRE PROTECTION
FP1.4b	ROOF PLAN PART A - FIRE PROTECTION
FP5.1	FIRE PROTECTION DETAILS
M0.1 M1.1a M1.1b M1.2a M1.2b M1.3a M1.3b M1.4a M1.4b M2.1a M2.1a M2.1b M2.2a M2.2b M2.3a M2.2b M2.3a M2.2b M2.3a M2.4a M2.4b M3.1 M4.1 M4.2 M4.3 M4.4 M4.5 M4.6 M5.1 M5.2 M5.3 M5.4 M5.5 M5.6 M6.1 M6.2 M6.3 M6.4 M7.1	MECHANICAL LEGEND AND ABBREVIATIONS FIRST FLOOR PLAN PART A - HVAC SECOND FLOOR PLAN PART B - HVAC SECOND FLOOR PLAN PART A - HVAC THIRD FLOOR PLAN PART A - HVAC THIRD FLOOR PLAN PART A - HVAC ROOF PLAN PART A - HVAC ROOF PLAN PART B - HVAC FIRST FLOOR PLAN PART B - PIPING/EXHAUST FIRST FLOOR PLAN PART B - PIPING/EXHAUST SECOND FLOOR PLAN PART B - PIPING/EXHAUST SECOND FLOOR PLAN PART B - PIPING/EXHAUST SECOND FLOOR PLAN PART B - PIPING/EXHAUST THIRD FLOOR PLAN PART B - PIPING/EXHAUST SECOND FLOOR PLAN PART B - PIPING/EXHAUST THIRD FLOOR PLAN PART B - PIPING/EXHAUST ROOF PLAN PART A - PIPING/EXHAUST ROOF PLAN PART A - PIPING/EXHAUST ENLARGED MECHANICAL PENTHOUSE ELEVATION ENLARGED MECHANICAL PLANS ENLARGED MECHANICAL PLANS MECHANICAL DETAILS MECHANICAL DETAILS MECHANICAL DETAILS MECHANICAL DETAILS MECHANICAL SCHEDULES MECHANICAL SCHEDULES MECHANICAL SCHEDULES MECHANICAL SCHEDULES MECHANICAL SCHEDULES MECHANICAL SCHEDULES

INDEX TO DRAWINGS PAGE 6 OF 10

M7.2 M7.3 M7.4 M7.5 M7.6 M7.7 M7.8 M7.9 M7.10 M8.1 M8.2	CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC CONTROL SCHEMATIC PIPING SCHEMATIC PIPING SCHEMATIC
E0.0 E0.1 E0.2 E0.3 E0.4 E0.5 E0.6 E0.7 E0.8 E0.9 E0.10 E0.11 E0.12 E0.13 E1.0a E1.0b E1.1a E1.0b E1.1a E1.2a E1.2b E1.3a E1.2b E1.3a E1.2b E1.3a E1.2b E1.3a E1.2b E1.3a E1.2b E1.3a E1.2b E1.3a E1.2b E2.1a E2.0b E2.1a E2.0b E2.1a E2.2b E2.3a E2.2b E2.3a E2.2b E3.3a E3.2b E3.1a E3.2b E3.2a E3.2b E3.3 E4.0a E4.0b E4.1a	ELECTRICAL LEGEND SINGLE LINE DIAGRAM SINGLE LINE DIAGRAM TELECOMMUNICATIONS RISER DIAGRAM ELECTRICAL DETAILS ELECTRICAL DETAILS ELECTRICAL DETAILS ELECTRICAL DETAILS ELECTRICAL DETAILS ELECTRICAL DETAILS PANEL SCHEDULES PANEL SCHEDULES PANEL SCHEDULES PANEL SCHEDULES ELECTRICAL SITE PLAN - POWER ELECTRICAL SITE PLAN - POWER ELECTRICAL SITE PLAN - DOWER ELECTRICAL SITE PLAN - POWER ELECTRICAL SITE PLAN - LIGHTING FIRST FLOOR LIGHTING PLAN - PART A SECOND FLOOR LIGHTING PLAN - PART B SECOND FLOOR LIGHTING PLAN - PART B THIRD FLOOR LIGHTING PLAN - PART B THIRD FLOOR LIGHTING PLAN - PART A SECOND FLOOR LIGHTING PLAN - PART A THIRD FLOOR LIGHTING PLAN - PART B THIRD FLOOR LIGHTING PLAN - PART B SECOND FLOOR LIGHTING PLAN - PART A THIRD FLOOR LIGHTING PLAN - PART B THIRD FLOOR COWER PLAN - PART A STAIR "B" LIGHTING DETAILS FIRST FLOOR POWER PLAN - PART A SECOND FLOOR POWER PLAN - PART B SECOND FLOOR POWER PLAN - PART A SECOND FLOOR POWER PLAN - PART A SECOND FLOOR POWER PLAN - PART B THIRD FLOOR POWER PLAN - PART B SECOND FLOOR MECH AUXILIARY PLAN - PART A ROOF POWER PLAN - PART B FIRST FLOOR MECH. AUXILIARY PLAN - PART A SECOND FLOOR MECH. AUXILIARY PLAN - PART A THIRD FLOOR MECH. AUXILIARY PLAN - PART A THIRD FLOOR MECH. AUXILIARY PLAN - PART A SECOND FLOOR MECH. AUXILIARY PLAN - PART A THIRD FLOOR MECH. AUXILIARY PLAN - PART A SECOND FLOOR MECH. AUXILIARY PLAN - PART A THIRD FLOOR MECH. AUXILIARY PLAN - PART B

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

INDEX TO DRAWINGS PAGE 7 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

E4.1b	SECOND FLOOR MECH PLAN - PART B
E4.2a	THIRD FLOOR MECH PLAN - PART A
E4.2b	THIRD FLOOR MECH PLAN - PART B
E4.3a	ROOF MECHANICAL PLAN - PART A
E4.3b	ROOF MECHANICAL PLAN - PART B
E4.4	MECHANICAL CONNECTION SCHEDULES
SEC1.0a	FIRST FLOOR SECURITY PLAN - PART A
SEC1.0b	FIRST FLOOR SECURITY PLAN - PART B
SEC1.1a	SECOND FLOOR SECURITY PLAN - PART A
SEC1.1b	SECOND FLOOR SECURITY PLAN - PART B
SEC1.2a	THIRD FLOOR SECURITY PLAN - PART A
SEC1.2b	THIRD FLOOR SECURITY PLAN - PART B
SEC1.3	ROOF SECURITY PLAN
EAV-100 EAV-101 EAV-102 EAV-201 EAV-202 EAV-203 EAV-205	LEGENDS AND NOTES DETAILS AND VIDEO WALL CONDUIT RISER DIAGRAMS FIRST FLOOR AUDIOVISUAL INFRASTRUCTURE SECOND FLOOR AUDIOVISUAL INFRASTRUCTURE THIRD FLOOR AUDIOVISUAL INFRASTRUCTURE FIRST & SECOND FLOOR AUDIOVISUAL INFRASTRUCTURE - BUILDING C
EAV-301	FIRST FLOOR RCP AUDIOVISUAL INFRASTRUCTURE

HISTORIC HOSPITAL- BUILDING C

T1.1 GENERAL NOTES

C SHEETS CIVIL DRAWINGS (PROVIDED IN SEPARATE SET OF DRAWINGS)

D1.1	SELECTIVE DEMOLITION PLANS
D1.1	

- D1.2 SELECTIVE DEMOLITION ELEVATIONS
- D1.3 SELECTIVE DEMOLITION PHOTOS
- A0.1 ARCHITECTURAL SITE PLAN

---SEE 'POLICE STATION/COURT' DRAWINGS---

A1.0-1.3 CODE SHEET & LIFE SAFETY PLANS ---SEE 'POLICE STATION/COURT' DRAWINGS---

- A2.1 FIRST FLOOR PLAN
- A2.2 SECOND FLOOR PLAN
- A2.3 THIRD FLOOR PLAN
- A2.4 FIRST & SECOND FLOOR DIMENSION PLAN
- A2.5 THIRD FLOOR DIMENSION PLAN

INDEX TO DRAWINGS PAGE 8 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

November 19, 2018	
A3.1	ROOF PLANS
A3.2	ROOF DETAILS
N0.2	Roof DETRIES
A4.1	FIRST FLOOR REFLECTED CEILING PLAN
A4.2	SECOND FLOOR REFLECTED CEILING PLAN
A4.3	THIRD FLOOR REFLECTED CEILING PLAN
714.0	
A5.1	NORTH & SOUTH BUILDING ELEVATIONS
A5.2	EAST & WEST BUILDING ELEVATIONS
A5.3	ENLARGED ENTRANCE ELEVATIONS
A6.1	LONGITUDINAL BUILDING SECTIONS
A6.2	TRANSVERSE BUILDING SECTIONS
A6.3	TRANSVERSE BUILDING SECTIONS
A6.4	TRANSVERSE BUILDING SECTIONS
A6.5	ENLARGED STAIR PLANS & DETAILS
A7.1	DOOR SCHEDULE & FRAME ELEVATIONS
A7.2	DOOR SCHEDULE (CONT.)
A8.1	FINISH SCHEDULE & CODES
A8.2	FINISH FLOOR PLANS
A9.1	INTERIOR ELEVATIONS
P0.1	PLUMBING LEGEND, NOTES AND ABBREVIATIONS
P1.1	FIRST FLOOR PLAN PART C - PLUMBING DEMO
P1.2	SECOND FLOOR PLAN PART C - PLUMBING DEMO
P1.3	THIRD FLOOR PLAN PART C - PLUMBING DEMO
P2.1	FIRST FLOOR PLAN PART C - PLUMBING
P2.2	SECOND FLOOR PLAN PART C - PLUMBING
P2.3	THIRD FLOOR PLAN PART C - PLUMBING
P2.4	ATTIC PLAN PART C - PLUMBING
P3.1	PLUMBING RISERS
P3.2	COLD WATER SCHEMATIC
P3.3	HOT WATER SCHEMATIC
P5.1	PLUMBING DETAILS
P6.1	PLUMBING SCHEDULES
FP2.1	FIRST FLOOR PLAN PART C - FIRE PROTECTION
FP2.2	SECOND FLOOR PLAN PART C - FIRE PROTECTION
FP2.3	THIRD FLOOR PLAN PART C - FIRE PROTECTION
FP2.4	ROOF PLAN PART C - FIRE PROTECTION
FP5.1	FIRE PROTECTION DETAILS
M0.1	MECHANICAL LEGEND AND ABBREVIATIONS
MD1.1	FIRST FLOOR PLAN PART C - HVAC DEMOLITION
MD1.2	SECOND FLOOR PLAN PART C - HVAC DEMOLITION

INDEX TO DRAWINGS PAGE 9 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

M1.2SECOND FLOOR PLAN PART C - HVACM1.3THIRD FLOOR PLAN PART C - HVACM1.4ROOF PLAN PART C - HVACM2.1FIRST FLOOR PLAN PART C - HVAC PIPING	
M2.2 SECOND FLOOR PLAN PART C - HVAC PIPING	
M2.3 THIRD FLOOR PLAN PART C - HVAC PIPING	
M2.4 ROOF PLAN PART C - HVAC PIPING	
M4.1 HVAC SUPPLY AND EXHAUST DUCT RISERS	
M5.1 MECHANICAL DETAILS	
M5.2 MECHANICAL DETAILS	
M5.3 MECHANICAL DETAILS	
M6.1 MECHANICAL SCHEDULES	
M6.2 MECHANICAL SCHEDULES	
M6.3 MECHANICAL SCHEDULES	
M7.1 CONTROL SCHEMATIC	
M7.2 CONTROL SCHEMATIC	
M7.3 CONTROL SCHEMATIC	
M7.4 CONTROL SCHEMATIC	
E0.0 LEGEND	
E0.1 SINGLE LINE DIAGRAM	
E0.2 ELECTRICAL DETAILS	
E0.3 ELECTRICAL DETAILS	
E0.4 PANEL SCHEDULES	
E0.5 PANEL SCHEDULES	
E0.6 TELECOMMUNICATIONS RISER DIAGRAM	
E1.0 LIGHTING PLAN - FIRST AND SECOND FLOOR	
E1.1 LIGHTING PLAN - THIRD FLOOR AND ROOF	
E2.0 POWER PLAN - FIRST AND SECOND FLOOR	
E2.1 POWER PLAN - THIRD FLOOR AND ROOF	
E3.0 AUXILIARY PLAN- FIRST AND SECOND FLOOR	
E3.1 AUXILIARY PLAN- THIRD FLOOR AND ROOF	
E4.0 MECHANICAL PLAN - FIRST AND SECOND FLOO)R
E4.1 MECHANICAL PLAN - THIRD FLOOR AND ROOF	
SEC1.0 SECURITY PLAN - FIRST AND SECOND FLOOR	
SEC1.1 SECURITY PLAN - THIRD FLOOR AND ROOF	

INDEX TO DRAWINGS PAGE 10 OF 10

Hattiesburg Public Safety Complex Hattiesburg, Mississippi

INDEX

ADVERTISEMENT TO BID MISSISSIPPI LANDMARK CONTRACTOR PREQUALIFICATION CRITERIA INDEX OF SPECIFICATIONS INDEX OF DRAWINGS FORM OF PROPOSAL SPECIFICATIONS

INDEX TO SPECIFICATIONS

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
VOLUME ONE			
DIVISION 0	DOCUMENTS		
	DOCOMENTS		
00 10 00	INSTRUCTIONS TO BIDDERS		
00 50 00	AGREEMENT FORM		
00 60 00	CONTRACT BOND		
00 65 00	CERTIFICATE OF INSURANCE INSTRUCTIONS		
00 70 00	GENERAL CONDITIONS		
00 80 00	SUPPLEMENTARY CONDITIONS		
00 90 00	ADDENDA		
00 95 00	ARCHITECT'S SPECIAL CONDITIONS		
DIVISION 1	GENERAL CONDITIONS		L
01 11 00	SUMMARY OF WORK		
01 20 00	ALLOWANCES		
01 21 00	PROJECT MEETINGS	 	
01 27 00	APPLICATIONS FOR PAYMENT		
01 29 00	SCHEDULE OF VALUES		
01 31 00	PROGRESS SCHEDULES		
01 33 00	SHOP DRAWINGS, PRODUCT DATA AND SAMPLES		
01 33 24	STRUCTURAL SUBMITTALS		
01 35 00	ALTERNATES		

INDEX TO SPECIFICATIONS PAGE 1 OF 8

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
SEISMIC REQUIREMENTS NON-STRUCTURAL COMPONENTS			
PROJECT COORDINATION			
ABBREVIATIONS AND STANDARDS			
STRUCTURAL SPECIAL INSPECTIONS			
EXISTING CONDITIONS			
1			
BUILDING AND STRUCTURE DEMOLITION			
CONCRETE			
CONCRETE			
CONCRETE FORMING AND ACCESSORIES			
CONCRETE FORMING AND ACCESSORIES			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING MASONRY UNIT MASONRY ASSEMBLIES CONCRETE UNIT MASONRY			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING MASONRY UNIT MASONRY ASSEMBLIES			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING MASONRY UNIT MASONRY ASSEMBLIES CONCRETE UNIT MASONRY CAST STONE MASONRY			
CONCRETE FORMING AND ACCESSORIES CONCRETE REINFORCING CAST-IN-PLACE CONCRETE INCIDENTAL CONCRETE PRECAST STRUCTURAL CONCRETE NON-SHRINK GROUTING MASONRY UNIT MASONRY ASSEMBLIES CONCRETE UNIT MASONRY			
	PROJECT COORDINATION ABBREVIATIONS AND STANDARDS STRUCTURAL SPECIAL INSPECTIONS CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS SUBSTITUTIONS AND PRODUCT OPTIONS STARTING OF SYSTEMS CUTTING AND PATCHING CLEANING PROJECT RECORD DOCUMENTS CONTRACT CLOSEOUT DIVISION ONE SUPPLEMENT	PROJECT COORDINATIONABBREVIATIONS AND STANDARDSSTRUCTURAL SPECIAL INSPECTIONSCONSTRUCTION FACILITIES AND TEMPORARY CONTROLSSUBSTITUTIONS AND PRODUCT OPTIONSSTARTING OF SYSTEMSCUTTING AND PATCHINGCLEANINGPROJECT RECORD DOCUMENTSCONTRACT CLOSEOUTDIVISION ONE SUPPLEMENTSUBSURFACE CONDITIONS	SEISMIC REQUIREMENTS NON-STRUCTURAL COMPONENTSPROJECT COORDINATIONABBREVIATIONS AND STANDARDSSTRUCTURAL SPECIAL INSPECTIONSCONSTRUCTION FACILITIES AND TEMPORARY CONTROLSSUBSTITUTIONS AND PRODUCT OPTIONSSTARTING OF SYSTEMSCUTTING AND PATCHINGCLEANINGPROJECT RECORD DOCUMENTSCONTRACT CLOSEOUTDIVISION ONE SUPPLEMENTSUBSURFACE CONDITIONS

INDEX TO SPECIFICATIONS PAGE 2 OF 8

Hattiesburg Public Safety Complex
Hattiesburg, Mississippi

			POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
05 21 00	STEEL JOIST FRAMING			
05 31 00	STEEL DECKING			
05 40 00	COLD-FORMED STEEL FRAMING			
05 41 00	COLD-FORMED EXTERIOR STEEL STUD FRAMING			
05 44 00	COLD-FORMED STEEL TRUSSES			
05 50 00	METAL FABRICATIONS			
05 52 13	HANDRAILS AND RAILINGS			
05 55 00	METAL STAIR NOSINGS			
DIVISION 6	WOOD & PLASTICS			
06 10 00	ROUGH CARPENTRY			
06 20 00	FINISH CARPENTRY			
06 41 00	ARCHITECTURAL WOOD CASEWORK			
DIVISION 7	THERMAL & MOISTURE PROTECTION			
07 13 26	SELF ADHERING SHEET WATERPROOFING			
07 19 00	WATER REPELLENTS			
07 21 00	THERMAL INSULATION			
07 21 23	LOOSE-FILL INSULATION			
07 25 00	WEATHER BARRIERS			
07 27 13	SELF-ADHERED SHEET MEMBRANE AIR BARRIERS, VAPOR IMPERM			
07 52 16	SBS-MODIFIED BITUMEN MEMBRANE ROOFING			
07 55 00	MULTI-LAYERED WATERPROOF FLOOR SURFACING			
07 62 00	SHEET METAL FLASHING AND TRIM			
07 84 00	FIRESTOPPING			
07 90 05	JOINT SEALERS			
07 95 13	EXPANSION JOINT COVER ASSEMBLIES			
DIVISION 8	OPENINGS			
08 11 13	HOLLOW METAL DOORS AND FRAMES			
08 14 16	FLUSH WOOD DOORS			
08 31 00	ACCESS DOORS AND PANELS	<u> </u>		
00 01 00				

INDEX TO SPECIFICATIONS PAGE 3 OF 8

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
08 33 23	HIGH PERFORMANCE OVERHEAD COILING DOORS		
08 34 59	VAULT DOORS		
08 34 63	DETENTION DOORS AND FRAMES		
08 43 13	ALUMINUM STOREFRONT AND DOORS		
08 44 13	GLAZED ALUMINUM CURTAIN WALLS		
08 52 13	ALUMINUM CLAD WINDOWS		
08 55 00	BULLET RESISTANT WINDOWS AND EQUIPMENT		
08 60 00	CURB MOUNT PLASTIC GLAZED UNIT SKYLIGHTS		
08 71 00	DOOR HARDWARE		
08 71 13	AUTOMATIC DOOR OPERATORS	 	
08 80 00			
08 85 00	FIRE RATED STEEL FRAMED ENTRANCES AND STOREFRONTS		
DIVISION 9	FINISHES		
09 21 16	GYPSUM BOARD ASSEMBLIES	 _	
09 22 36.23	METAL LATH PORTLAND CEMENT PLASTERING		
09 24 00			
09 25 00	SOUND ABSORBING PLASTER SYSTEM		
09 25 00 09 30 00	SOUND ABSORBING PLASTER SYSTEM TILING		
09 25 00 09 30 00 09 51 00	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS		
09 25 00 09 30 00 09 51 00 09 64 23	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 00	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 00 09 68 13	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 00 09 68 13 09 69 00	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 13 09 69 00 09 84 10 09 84 53 09 91 13	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING SOUND ABSORPTIVE WALL PANELS		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 00 09 68 13 09 69 00 09 84 10 09 84 53	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING SOUND ABSORPTIVE WALL PANELS SOUND BARRIER MULLION TRIM CAP		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 13 09 69 00 09 84 10 09 91 13 09 91 23	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING SOUND ABSORPTIVE WALL PANELS SOUND BARRIER MULLION TRIM CAP EXTERIOR PAINTING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 13 09 69 00 09 84 10 09 84 53 09 91 13	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING SOUND ABSORPTIVE WALL PANELS SOUND BARRIER MULLION TRIM CAP EXTERIOR PAINTING		
09 25 00 09 30 00 09 51 00 09 64 23 09 65 00 09 65 19 09 65 66 09 68 13 09 69 00 09 84 10 09 84 53 09 91 13 09 91 23	SOUND ABSORBING PLASTER SYSTEM TILING ACOUSTICAL CEILINGS WOOD FLOORING RESILIENT FLOORING AND BASE RESILIENT RUBBER TILE RESILIENT ATHLETIC FLOORING CARPET TILE CARPETING ACCESS FLOORING SOUND ABSORPTIVE WALL PANELS SOUND BARRIER MULLION TRIM CAP EXTERIOR PAINTING		

Albert & McCleskey Associates Architects December 30, 2016

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
10 14 19	DIMENSIONAL LETTERS		
10 21 13	STAINLESS STEEL TOILET COMPARTMENTS		
10 22 19	DEMOUNTABLE PARTITIONS		
10 26 00	CRASH RAILS		
10 26 05	CORNER GUARDS		
10 26 41	BULLET RESISTANT COMPOSITE (FIBERGLASS)		
10 28 00	TOILET, BATH AND LAUNDRY ACCESSORIES		
10 28 14			
10 44 00	FIRE EXTINGUISHERS, CABINETS AND ACCESSORIES	 	
10 51 13	METAL LOCKERS METAL CANOPIES		
10 73 00 10 75 00	FLAGPOLES		
10 7 5 00	FLAGFOLES		
DIVISION 11	EQUIPMENT		
11 13 19.13	LOADING DOCK LEVELERS		
DIVISION 12	FURNISHINGS		
12 35 53	STAINLESS STEEL LABORATORY CASEWORK		
12 36 00	COUNTERTOPS		
DIVISION 14	CONVEYING EQUIPMENT		
14 21 05	ELECTRIC TRACTION ELEVATOR A 2500#		
14 21 10	ELECTRIC TRACTION ELEVATOR B 5000#		
VOLUME TWO			
DIVISION 21	FIRE SUPPRESSION SYSTEMS		
21 13 00	FIRE SUPPRESSION SYSTEMS		
DIVISION 22	PLUMBING		

INDEX TO SPECIFICATIONS PAGE 5 OF 8

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
00.44.40			
22 11 16 22 13 16	DOMESTIC WATER PIPING SANITARY WASTE AND VENT PIPING	_	
22 13 16	SANTARY WASTE AND VENT PIPING STORM DRAINAGE PIPING	_	
22 14 10	PLUMBING SPECIALTIES		
22 34 00	FUEL-FIRED COMMERCIAL WATER HEATERS	_	
22 40 00	PLUMBING FIXTURES		
DIVISION 23	HEATING, VENTILATING AND AIR CONDITIONING		
23 00 10	MECHANICAL GENERAL PROVISIONS		
23 05 00	BASIC MECHANICAL MATERIALS AND METHODS		
23 05 13	MOTORS AND CONTROLLERS		
23 05 16	PIPING SPECIALTIES		
23 05 23	VALVES		
23 05 29	HANGERS AND SUPPORTS		
23 05 33			
23 05 48	MECHANICAL SOUND AND VIBRATION CONTROL		
23 05 53 23 05 93	MECHANICAL SYSTEM IDENTIFICATION TESTING, ADJUSTING AND BALANCING		
23 05 93	DUCT INSULATION		
23 07 19	PIPING AND EQUIPMENT INSULATION	_	
23 09 00	ENERGY MANAGEMENT AND CONTROL SYSTEM		
23 09 13	EMCS BASIC MATERIALS AND DEVICES		
23 09 16	EMCS OPERATOR INTERFACES		
23 09 19	EMCS FIELD PANELS		
23 09 23	EMCS COMMUNICATION DEVICES		
23 09 26	EMCS SOFTWARE AND PROGRAMMING		
23 09 29	EMCS POINTS AND SEQUENCE OF OPERATION		
23 09 33	EMCS SYSTEM COMMISSIONING		
23 11 00	FUEL GAS PIPING		
23 21 12	HEATING AND COOLING PIPING		
23 21 23	PUMPS		
23 23 00	REFRIGERANT PIPING		
23 25 00	WATER TREATMENT – CLOSED SYSTEM		
23 31 13	DUCTS		

			POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
23 33 00	DUCT ACCESSORIES			
23 34 00	FANS			
23 36 00	AIR TERMINAL UNITS			
23 37 00	AIR OUTLETS AND INLETS			
23 40 00	AIR CLEANING DEVICES			
23 52 16	CONDENSING BOILERS			
23 64 26	SCREW WATER CHILLERS			
23 73 13	MODULAR INDOOR CENTRAL STATION AIR HANDLING UNITS			
23 73 15	OUTDOOR AIR HANDLING UNITS			
23 81 16	SPLIT SYSTEM VRF HEAT PUMP EQUIPMENT			
23 81 23	COMPUTER ROOM AIR-CONDENSERS			
23 81 43	AIR SOURCE UNITARY DUCTLESS SPLIT-SYSTEMS			
23 82 19	FAN COIL UNITS			
23 82 39	UNIT HEATERS			
	•	•		
DIVISION 26	ELECTRICAL			
		_		
26 05 11	ELECTRICAL GENERAL			
26 05 19	LOW-VOLTAGE POWER CONDUCTORS AND CABLES			
26 05 26	GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS			
26 05 33	RACEWAYS, OUTLET BOXES AND JUNCTION BOXES FOR ELEC SYS			
26 09 23	SWITCHES AND RECEPTACLES			
26 09 25	OCCUPANCY SENSORS			
26 22 00	TRANSFORMERS			
26 24 00	PANELBOARDS			
26 26 00	SWITCHBOARD			
26 28 00	DISCONNECTS & SEPARATELY-MOUNTED CIRCUIT BREAKERS			
26 32 14	POLICE EMERGENCY/STANDBY POWER SYSTEMS GENERATOR SET			
26 36 23	AUTOMATIC TRANSFER SWITCHES			
26 41 00	LIGHTNING PROTECTION SYSTEM			
26 43 00	SURGE PROTECTIVE DEVICES (SPD)			
26 51 00	LIGHTING			
26 51 01	MOTION DETECTORS			
DIVISION 27	COMMUNICATIONS			

INDEX TO SPECIFICATIONS PAGE 7 OF 8

		POLICE/COURT "A & B"	HISTORICAL HOSPITAL "C"
27 05 13	CABLE TELEVISION		
27 30 00	TELEPHONE AND DATA SYSTEMS		
27 51 13	PAGING SYSTEM		
27 51 23	INTERCOM SYSTEM		
DIVISION 28	ELECTRONIC SAFETY AND SECURITY		
28 20 00			
28 23 23	CLOSED CIRCUIT TELEVISION (CCTV) SYSTEM		
28 30 00	ACCESS CONTROL SYSTEM		
28 31 00	POLICE/COURT FIRE ALARM SYSTEM		
DIVISION 31	EARTHWORK		
24.05.00			
31 05 00			
31 11 00	SITE PREPARATION		
31 22 19			
31 23 19	EARTHWORK FOR STRUCTURES (POLICE/COURT)	 	
31 31 16		 	
31 34 21 31 91 00	AGGREGATE PIER REINFORCEMENT	 	
319100	LANDSCAPE WORK		
DIVISION 32	EXTERIOR IMPROVEMENTS		
32 31 13	CHAIN LINK FENCES		
DIVISION 33	UTILITIES		
33 39 13	MANHOLES		
33 10 00	WATER DISTRIBUTION		
33 30 00	SANITARY SEWER		
33 14 00	SEWER/WATER UTILIY – TRACE WIRE		

END OF INDEX OF SPECIFICATIONS

INDEX TO SPECIFICATIONS PAGE 8 OF 8



P.O. BOX 17678 HATTIESBURG, MS 39404

P 601.583.6500 F 601.583.6503

February 13, 2019

City of Hattiesburg

RE: Hattiesburg Public Safety Complex

ATTN: City of Hattiesburg Administration

Dear City:

Please accept this letter as Hanco Corporation's proposal to value engineer bid proposal dated January 3, 2019. The following is a list of items proposed to reduce bid price to a lump sum amount of \$26,500,000.00. All of these items have been previously discussed with city representatives in our value engineering meetings.

- 1. Contract time will be extended to 1080 days. Omit liquidated damages from contract documents.
- 2. The City of Hattiesburg will provide all third-party special inspectors per the I.B.C.
- 3. The contract amount for Hardware Allowance is \$150,000.00 only. The City must acknowledge that they are responsible for the entire acoustical systems, sound panels and audio visual, which are all necessary for the function of the court room. audio visual, crime scene lab, light fixture, stained glass, toilet accessories and stained glass lettering allowances are removed from the contract.
- 4. City will pay for all construction power.
- 5. City will pay for all water, water taps, sewer and sewer taps.
- 6. Delete mock ups from contract. Mock ups will be done in place with quality control by Contractor, Architect and Envelope Specialists.
- 7. Fence Changes:
 - a. 16' Aluminum track gates change to 16' pipe cantilever gates.
 - b. Max 2200 D.C. Swing Gate Operator. Change Max 2200 D.C. Slide Operator.
- 8. Parking striping to standard paint in lieu of thermoplastic paint specified.

- 9. Structural Steel Changes:
 - a. Delete bollard covers. Bollards will be standard paint.
 - b. Delete supports for smoke evacuation system, which is omitted.
 - c. Lower parapet wall on east, north and south as much as possible.
 - d. If possible, simplify steel railing from what is shown; this must be approved by architect.
- 10. Remove the third-floor pedestrian bridge as approved by the City of Hattiesburg Code Official. Official ruled this will not result in a dead-end corridor as described by the I.B.C.
- 11. Omit the building smoke evacuation system as per the approval of the City of Hattiesburg Code Official.
- 12. Millwork Changes:
 - a. Delete references to wood on walls of elevator shaft. This wall will be painted gypsum board.
 - b. Delete all formica wall and metal ceiling panels. All walls will be painted gypsum and ceiling will be acoustical 2'x2'.
 - c. Change all quartz tops to formica tops. Owner must acknowledge that the formica tops are not as durable as quartz and they do have a tendency to chip.
 - d. All cabinets to be formica covered standard.
- 13. Delete iscolyene insulation from contract. All insulation will be standard fiberglass.
- 14. Delete references to paint in contract for mechanical room penthouse floor. Floor to be sealed with penetrating sealer.
- 15. Change fire proofing sprayed on application over sally port ceiling to another system which will still provide a 1-hour fire rating on the steel beams and metal deck.
- 16. Glass & Aluminum framing changes:
 - a. Delete references in contract with regards to high impact. All framing and glass to be standard aluminum and glass as approved by the City of Hattiesburg Code Official.
 - b. Delete or change all interior and exterior elevations of glass and framing system to revised elevations in drawings (to be provided by Architect). This change will affect most all of the exterior curtain wall system as well as interior storefront systems. A substantial amount of glass and aluminum framing will be deleted from project.

- 17. Metal Stud Framing/Gypsum Board/Acoustical Ceilings:
 - a. Omit reveals except expansion joints, specialty ceilings and formica wall coverings.
 - b. All exterior walls and interior partitions will be standard metal framing, 5/8" gypsum board and acoustical insulation.
 - c. All interior ceilings are to be standard 2' x 2' acoustical flat ceilings. Delete all special ceilings.
 - d. Delete all reveal moldings in gypsum board.
- 18. Plastering:
 - a. Delete interior plastering in Historic Building except where it is economical.
- 19. Flooring & Ceramic Tile Changes:
 - a. All flooring in new public safety building will be LVT and/or carpeting. LVT will be a medium grade #2 tile and the carpet will have a \$25/yard allowance. Owner acknowledges that changing to LVT in the lobby will create noise issues.
 - Remove all ceramic or porcelain wall tile and floor tile except the public bathroom floors and 4-foot wainscot on the wet wall of the public restrooms. All remaining walls will be epoxy paint on water proof gypsum board.
- 20. General Contractor will have option to restore terrazzo in Historic Building or cover it. Omit terrazzo in new public safety building. Stair tread will be either solid wood or concrete pans that Contractor will select based on Architect's recommendation to meet I.B.C.
- 21, Omit signage from contract. Owner will supply and install all signage.
- 22. Change all toilet partitions to a standard plastic-type partition.
- 23. Omit evidence lockers from contract. Owner acknowledges that they will supply And install the evidence lockers to meet the building program.
- 24. Omit compact evidence shelving. Owner acknowledges that they will supply and install to meet the building program.
- 25. Mechanical Changes: (see attached letter from Pat L. McKenzie, Inc.)
- 26. The mechanical system controls will be provided by the City of Hattiesburg. The City will bid controls out and the Contractor will coordinate installation.
- 27. Electrical Changes:
 - a. All V.E. items per Chain Electric (see attached Chain Electric Value Engineering letter)

- 28. Omit wall guards.
- 29. Grass sod will be furnished and installed by the City of Hattiesburg.
- 30. All grassing, landscaping, irrigation and irrigation sleeves will be installed by the City of Hattiesburg.
- 31. Delete all cast iron downspout boots.
- 32. Delete freight elevator. All shafts will be installed for future install.
- 33. Change detention security doors to 12 ga security hollow metal frames and 12 ga metal doors as approved by the Hattiesburg Police.
- 34. The City of Hattiesburg Code Official ruled the drawing modifications required for all Of the above cuts can be produced as the project moves forward.
- 35. Omit all concrete sidewalks, concrete curbs and gutters, and all site work concrete on North side of Historic Building. City will construct this area in future Memorial Design or under their present site work contract.
- 36. Omit stamped concrete from site design.
- 37. Omit (2) Lighted flag poles and concrete surrounds on North side of Historic Building.

It is Hanco Corporation's intent to construct this building and go through the building process without any change orders. Hanco Corporation will diligently work with City representatives as well as design professional representatives to avoid potential change orders.

Additional added scopes of work or unforeseen conditions or covered conditions that affect cost will have to be addressed if and when they are possibly encountered.

Hanco Corporation requires the right to sign off on and approve all revised architectural drawings generated to clarify value engineered items.

Sincerely. Hanco Corporation

Chris Hudson

EXHIBIT D PATL MCKENZIE, INC. MECHANICAL CONTRACTOR P.O. Box 278 Ellisville, MS 39437 Phone: (601) 4n-3423 Fax: (601) 4n-3496

February 11, 2019 To: Hanco Corporation Project: Public Safety Complex Hattiesburg, MS Division 22 -Plumbing Division 23 - HVAC

Gentlemen:

We offer the following value engineering items for the above project for a price reduction

- 1. Change Sanitary and Storm Drain Piping from Cast Iron to PVC-DWV (With Firewrap Where Required)
- 2. Change Condensate Drain Piping from Copper DWV to PVC-DWV
- 3. Change Domestic Water Piping from Copper to Aquatherm & PEX
- 4. Change Chilled Water Piping to Aquatherm
- 5. Change Heating Water Piping to Aquatherm
- 6. Pipe Insulation Thickness to be Per Aquatherm's Recommendations
- 7. Fiberglass Insulation to be used on Aquatherm Chilled Water Pipe in lieu of Foam Glass
- 8. Various Changes to Plumbing Fixtures to Standard Commercial Fixtures
- 9. Changed Specified Recirculation Pumps to Taco 2400-45-3P and 1915D-1-18-1
- 10. Remove Smoke Evacuation System
- 11. Change Site Utility Water Main Piping from Ductile Iron to C900 Pipe with MJ Fittings
- 12. Delete Magnesium Grounding Anodes and Access Boxes
- 13. Reduce the Casing Size of All AHUs. All Specified Capacities and Features Will Be Met.
- 14. Delete Multiple Supply Fans for AHU-3, 4, & 6, and the Multiple Relief Fans for AHU-6, and Provide Single Direct Drive Plenum Fans in Both the Supply and Relief Fan Sections. All Performance Criteria will be met as Designed.
- 15. Reduce Pipe Chase Enclosures from 36 Inches to 24 Inches
- 16. Change the Two (2) Air Cooled Rotary Chillers to Two (2) Air Cooled Scrolled Chillers
- 17. Change the Two (2) Outside Air Units to One (1) Outside Air Unit
- 18. Delete the Chilled Water BTU Meter, Heating Water BTU Meter, Natural Gas Meter, and Laptop Computers from the Control Specifications
- 19. Delete Low Pressure Duct Testing
- 20. Delete Coordination Drawings
- 21. Change All Grilles from Aluminum to Steel
- 22. Change Square Cone Diffusers from Removable Core to Affixed Core
- 23. Change Slot Diffusers to Lay In

Respectfully Submitted By: Pat L. McKenzie, Inc. EXHIBIT D



1308 W. Pine Street P. O. Box 2058 Hattiesburg, MS 39403-2058 Telephone (601) 545-3800 FAX (601) 584-8320 e-mail: bchain@bchain.com

February 13, 2019

Hanco Corporation Fax: 601-583-6503 Attn: Chris Hudson

Re: Electrical Value Engineering for Hattiesburg Public Safety Complex Project – City of Hattiesburg, MS (Revised from Electrical VE Proposal, Dated January 22, 2019)

Please accept the following as our electrical value engineered proposal to reduce the overall cost of electrical installation for the Hattiesburg Public Safety Complex Project – Police Department, Municipal Court, and Historic Hospital Buildings.

ELECTRICAL VALUE ENGINEERED OPTIONS

LIGHT FIXTURES AND LIGHTING CONTROLS PACKAGE

POLICE AND COURT BUILDING:

*Change recessed linear LED fixtures types K4RG, K4WW, KR2L, KR4L, KR4H, and KR4W to recessed layin flat panels (2x4, 2x2, or 1x4).

*Change recessed 2x4/2x2 lay-in fixtures types S and S2 to recessed lay-in flat panels.

*Change exit fixtures types X1, X2, XR1, and XR2 to standard commercial grade thermoplastic exits.

*Change fixtures types C1, C2, and D dimming divers from Eldo 0-10%/1% dimming to Phillips 0-10%/1% dimming.

*Change linear pendant fixture type K4ID to surface mount flat panels. HISTORIC HOSPITAL BUILDING:

*Change recessed linear LED fixtures types KK1 and KK2 to recessed lay-in flat panels (2x4, 2x2, or 1x4).

*Change exit fixtures type X1 and X2 to standard commercial grade thermoplastic exits.

*Change fixture type CC1 dimming drivers from Eldo 0-10%/1% dimming to Philips 0-10%/1% dimming.

*Change recessed 2x4 lay-in fixture type SS to recessed flat panel lay-ins.

*Change pendant fixture type AA to Williams SDI5 Series pendants

DISTRIBUTION GEAR PACKAGE

*Change all switchboard and panelboard buss from copper to aluminum.

*Change dead-front, door-in-door 4 piece hinged panelboard covers to standard type.

GENERATOR/ATS PACKAGE

*Change ATS manufacturer from ASCO to EATON.

*Received better weatherproof generator enclosure price from different manufacturer.

LIGHTNING PROTECTION SYSTEM PACKAGE

*Eliminate Lightning Protection System in its entirety.

TELEPHONE, DATA, CATV, AND POWER RACEWAY SYSTEM

*Eliminate as specified conduit raceway system installed from each device to communications backboards and provide conduit raceways stubbed up from each device to above accessible ceiling and a J-hook wire management system above ceiling for routing of cables to communications backboards. This will cut down on a substantial amount of conduit and help reduce congestion above the ceilings. *Use MC type cable for power branch circuits from centrally located homerun J-boxes to device outlets where permissible, instead of hard pipe and wire.

*Price does not include tax or bond.

*All clarifications and qualifications stated in Original Electrical Proposal from Chain Electric Company, dated 1-3-2019, still apply.

*Value engineered electrical options must be acceptable to and approved by Owner, Project Architect, and Project Electrical Engineer.

*If accepted, the Electrical Value Engineered Proposal amount shall be deducted from Chain Electric Company's original base bid proposal amount, dated 1-3-2019.

If you have any questions or concerns, please call me at 601-545-3800 or 601-596-5152.

Thank you, 20

Harvey Simpons Manager Commercial and Industrial Division